सत्यमेव जयते

राजस्थान राजपत्र विशेषांक	RAJASTHAN GAZETTE Extraordinary
साधिकार प्रकाशित	Published by Authority
कार्तिक 20, मंगलवार, *शाके* 1947- नवम्बर 11, 2025 Kartika 20, Tuesday, Saka 1947- November 11, 2025	

भाग-7

विभिन्न विभागों में प्रदायों के लिए टेण्डर मांगने की सूचनाओं को सम्मिलित करते हुये सार्वजनिक और निजी विज्ञापन आदि।

Energy Department

NOTIFICATION

Jaipur, October 27, 2025

No. F.12(12)Energy/2021 .-In exercise of powers conferred by Sub para 3.3 of para 3 of the Guidelines for Tariff Based Competitive Bidding (TBCB) for Transmission Service circulated by Ministry of Power (MoP), Government of India, under Section 63 of Electricity Act, 2003, published in the Gazette of India Notification / Resolution dated 10th August, 2021, the State Government hereby appoints M/s. REC Power Development and Consultancy Limited as Bid Process Coordinator (BPC) for the development of Intra-State Transmission Projects, as mentioned in the Table below, through Tariff Based Competitive Bidding (TBCB) in Rajasthan.

1. 765 kV GSS Jaisalmer (Teliwara) alongwith associated transmission system:

S No.	**Details of work (Name of the Sub-Station /Line)**	**Estimated Cost (in Rs. Crore)**
1	A. Substation 765/400 kV Substation Jaisalmer (Teliwara) [3x 1500 MVA 765/400 kV Transformer, 3x80 MVAR Bus Reactor, 1x125 MVAR, 420 kV Bus Reactor, 2 x1 Nos. 765 kV Line Bay with 3x80 MVAR Switchable Line Reactors in each circuit & at each end, 3 Nos. of 765 kV Transformer Bays, 1 No. Bus Reactor Bay, 16 Nos. 400 kV Bays] including 2x±150 MVAR STATCOM B. Bay • 2 nos. 765 kV line bays at 765 kV GSS Kankani for D/C Jaisalmer-Kankani line (AL-59 Zebra) • 2 nos. 400 kV line bays at 400 kV GSS Jaisalmer-II for D/C Jaisalmer-Jaisalmer-II line [Already constructed by RVPN] C. Lines • 765kV D/C Kankani-Jaisalmer (Teliwara) line using Hexa Zebra AL-59 conductor (163 kms.)	A. Sub – Stations 1039.87 B. Bay 44.71 NIL C. Lines 1322.13 147.41

	• 400 kV D/C Jaisalmer-II - Jaisalmer (Teliwara) line (Quad Moose) (41 kms.) • LILO of both the circuits of 400 kV D/C Ramgarh-Akal line at Jaisalmer (Teliwara) (Twin Moose) (88 kms.)	189.04
Total (in Rs. Cr)		**2743.16**

2. 400/220 kV Grid Sub-Station at Dholpur along with associated transmission system:

S No.	**Details of work (Name of the Sub-Station /Line)**	**Estimated Cost (in Rs. Crore)**
1	A. Sub – Station i. Construction of 2X500 MVA, 400/220 kV Grid Sub-Station at Dholpur along with 420 kV, 125 MVAR Bus Reactor B. Associated Bay Works i. 400 kV Half Dia at 400 kV GSS Hindaun C. Lines i. 65 KM LILO of PGCIL's 400 kV S/C Bassi – Agra line at 400 kV GSS Dholpur. ii. 0.4 KM 400 kV S/C Line from location no. 780 of existing 400 kV S/C Hindaun – DCPP line to 400 kV GSS Dholpur to charge on 400 kV level. iii. 30 KM LILO of 220 kV S/C Dholpur (DCPP) – Bharatpur line at proposed 400 kV GSS Dholpur iv. 0.4 KM 220 kV S/C Line from location no. 781 of existing 400 kV S/C Hindaun – DCPP line to 400 kV GSS Dholpur to Charge on 220 kV level.	A. Sub – Station i. 234.68 [B. Associated Bay Works i. 6.77 C. Lines i. 173.26 ii. 1.07 iii. 22.89 iv. 0.18
Total(in Rs. Cr)		**438.84**

The appointment of the Bid-Process Coordinators is subject to the conditions laid down in the Guidelines issued in this regard by the Ministry of Power (MoP), GoI, amended from time to time.

By order of the Governor,

Sourabh Swami ,
Joint Secretary to Government.

राज्य केन्द्रीय मुद्रणालय, जयपुर।